Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 1 of 9**
Date 1-8-19	Approx 2809 sq ft + decks		
Description	**Amount**	**Description**	**Amount**
Lower walls		**Lower walls con't**	
2 x 4 pt	50 LF	P drives / wedgies	$100.00
2 x 6 pt	250 LF	ECCQ66	3
2 x 4 - 104-5/8	50	CCQ66	1
2 x 6 - 104-5/8	90	5/8 x 7” if cb66	12 B + 12 N +24 W
2 x 4 braces	15/20' 8/12'	6 Mill	1000 sq ft
2 x 4	150 LF	sill seal	250 LF
2 x 6	400 LF	1/2" or 5/8" W dipped	100 plate washers
2 x 6 ponywall	10/12'	1/2" or 5/8" nuts	Typical by concrete sub
4 x 4	3/10'	**No Holdowns shown**	
4 x 6	4/8' 4/10'		
6 x 6	8/10'		
6 x 8	2/12'		
6 x 12	1/16'		
5-1/2 x 12 glb	1/14' 1/16'		
5-1/2 x 16 PSL	1/30'		
1/2" cdx / osb ???	22 shts		
EPC66 dipped	2		

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 2**
Date 1-8-19	Approx 2809 sq ft + decks		
Description	**Amount**	**Description**	**Amount**
2nd floor joists		**Front porch**	
11-7/8 TJI joists	3/12' 1/13' 2/15' 9/14' 13/18'	6 x 6 pt	1/18'
(verify series ??)	6/20' 19/24'		
		6 x 12 pt	1/18'
11-7/8" LVL rim stock	200 LF		
		HUC612 dipped	3
1-1/2 x 11-7/8 LSL blks	90 LF		
		ACE6 dipped	2
1-3/4 x 11-7/8" LVL	10/13' 3/15' 1/14' 1/8' 1/12'		
	2/18' 5/20' 2/34'	5/8 x 7” if cb66	2 B + 2 N +4 W
2 x 4	100 LF		
2 x 6	150 LF		
2 x 12 landing	10/8'		
3/4" T & G ply ????	52 shts		
2 x 12 stringers	3/18'		
1-1/8" bullnose treads	15 – 4' pieces		
11-7/8 TJI hangers	2		
(verify series ??)			
A35	30		
U210	20		
Big glue	1-1/2 boxes		
U210-2	16		

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 3**
Date 1-8-19	Approx 2809 sq ft + decks		
Description	**Amount**	**Description**	**Amount**
2nd level walls		**3rd floor joists**	
2 x 4 – 104-5/8	170	14 TJI joists	4/19' 5/23' 7/24' 10/36'
		(verify series ??)	
2 x 6 – 104-5/8	160		
		3-1/2 x 14” PSL	1/27'
2 x 4 braces	15/12' 12/20'	14” LSL blks	60 LF
2 x 4	450 LF	14" LVL rim stock	160 LF
2 x 6	900 LF	1-3/4 x 14" LVL	1/20' 1/23' 6/24'
2 x 6 tall walls	70/18'	2 x 4	100 LF
4 x 4	11/10'	2 x 6	200 LF
4 x 6	3/10'	2 x 12 landing	10/8'
4 x 8	1/14' 1/10' 1/8'	3/4" T & G ply ????	38 shts
6 x 6	4/10' 2/8' 1/18'	2 x 12 stringers	3/18'
6 x 8	112 LF	1-1/8" bullnose treads	15-4' pieces
6 x 10	1/10'	14” TJI hangers	3
		(verify series ??)	
1/2" cdx / osb	60 shts		
		1-3/4 x 14 LVL hanger	2
5-1/2 x 15 glb	1/10'		
		A35	30
ECCQ44	2		
		U210	10
MSTA36	2		
		U210-2	9
CCQ44	1		
No Hd's shown		Big glue	1 box

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 4**
Date 1-8-19	Approx 2809 sq ft + decks		
Description	**Amount**	**Description**	**Amount**
3rd level walls		**Roof**	
2 x 4 - 92-5/8	250	2 x 4 sheeting/gutter	150 LF
		walk scabs steep pitch	
2 x 6 - 92-5/8	135		
		2 x 4	150 LF
2 x 4 braces	15/12'		
		2 x 6	4/16' 8/12'
2 x 4	800 LF		
		2 x 8	1/12' 2/20'
2 x 6	700 LF	2 x 10	1/8'
		2 x 12	7/18'
4 x 6	1/8'		
		2 x 8 barges ??	1/10' 2/14' 2/16' 1/18' 3/20'
6 x 6	1/8'		
		1 x 4 barge trim ?? size	1/10' 2/14' 2/16' 1/18' 3/20'
6 x 8	38 LF		
		2 x 8 fascia	100 LF
6 x 12	1/10'		
		1/2" cdx or osb	68 shts
1/2" cdx / osb	50 shts		
		1/2" ccx 2' E +2' B cuts	14 shts
5-1/2 x 13-1/2 glb	1/11'		
		2 x 10 vented BB	5
MSTA36	2		
		A35	30
No Hd's shown			
		H2.5A	5
		Roof anchors ???	2
		Spray paint	1 can
		1/2" ply clips	300
		U210-2	4
		U24	6

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 5**
Date 1-8-19	Approx 2809 sq ft + decks		
Description	**Amount**	**Description**	**Amount**
Window set		**Siding con't**	
Caulk	24 tubes	1 x 4 belly trim	94 LF
9" sticky moist	450 LF	post wrps	Shows stone work
9" staple moist	600 LF	2 x 8 garage wrps	4/8' 2/12'
corner shields	90 pieces	5/4 x 8 gar hd trim	Shows stone work
Siding	**LOTS of stone**	Moist stop / caulk	$500 final finish
hardi bevel ??	2000 sq ft	5/4 x win hd flashing	180 LF
Wall shingles	500 sq ft	tin shingles (+ or -)	200
5/4 x 4 corner ??	180 LF (lots of stone corner)	Bldg paper	2500 sq ft
5/4 x 4 win wraps	600 LF	Light / hose / elect blks	$120 allotment
2 x 2	90 LF	Spray paint	3 cans
1/2" ccx	2 – 4' x 10' + 1 – 4' x 8'	18 x 24" gable vent	3
1 x 2 soffit trim	100 LF		
		Gable knee braces	
eave frz. ???	90 LF		
		6 x 6 outlooks ???	1/12' material size ??
gable frz. ???	140 LF		
		6 x 6 knees	1/12' material size ??
1 x 6 bm bot wraps	1/14' 1/16'		
		2 x 6 base plates	1/12' material size ??
5/4 x 12 bm wraps	2/16' 2/14'		
		Hardware	$40.00
5/4 x 12 belly band	94 LF + flashing		

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 6**
Date 1-8-19	Approx 2809 sq ft + decks		
Description	**Amount**	**Description**	**Amount**
Front porch deck		**Front porch deck finish**	
6 x 6 pt	on porch list	2 x 2 cedar pickets	60/3'
6 x 6 pt knee braces	1/8'	2 x 6 cedar	30 LF
4 x 4 pt	1/20'	2 x 4 cedar	60 LF
2 x 8 pt	3/8' 5/10' 2/12'	4 x 4 cedar	3/8'
4 x 8 pt	2/8'	2 x 6 cedar decking ??	160 sq ft
6 x 12 pt bms	1/18'	5/4 x 10 trim band	26 LF
2 x 12 pt stringers	4/18'	1/2 x 5" dipped lags	4 B +4 W
2 x 4 pt strongs	4/18'	Misc hardware	$100.00
1/4” x 3-1/2 sds dipped	40	DTT2Z	4
U210-2 dipped	9	1/2 x 7" bolts dipped	4 B + 4 N +8 W
U26 dipped	13		
BC44 dipped	4 dipped		
deck flashing dipped	20 LF		
HUC612 dipped	4		
ABU44 dipped	4		
5/8 x 5” wedgies	4 B		
HUC48 dipped	4		

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 7**
Date 1-8-19	Approx 2809 sq ft + decks		
Back porch deck		**Dining porch deck**	
6 x 6 pt	1/8'	6 x 6 pt	1/10'
2 x 8 pt	13/8' 3/16'	6 x 6 pt knee braces	1/8'
6 x 8 pt bms	1/16'	2 x 8 pt	6/8' 3/14'
2 x 12 pt stringers	Not shown	6 x 12 pt bms	1/18'
2 x 4 pt strongs	Not shown	¼ x 3-1/2 SDS dipped	20
¼ x 3-1/2 SDS dipped	30	U26 dipped	12
U26 dipped	13	deck flashing dipped	20 LF
deck flashing dipped	20 LF	HUC612 dipped	3
ABU66 dipped	3	5/8 x 7" if cb66	2 B + 2 N +4 W
5/8 x 5” wedgies	3 B	BC66 dipped	1
BC66 dipped	3		
Back porch deck finish			
2 x 6 cedar decking ??	19/16'		
5/4 x 10 trim band	2/8' 1/16'		

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 8**
Date 1-8-19	Approx 2809 sq ft + decks		
Dining deck finish		**Bedroom 1 porch deck**	
2 x 2 cedar pickets	28/3'	6 x 6 pt knee braces	1/8'
2 x 6 cedar	1/18'	6 x 6 pt	1/8'
2 x 4 cedar	2/18'	2 x 8 pt	6/8' 3/14'
4 x 4 cedar	1/12' 1/8'	6 x 12 pt bms	1/18'
2 x 6 cedar decking ??	9/14'	¼ x 3-1/2 SDS dipped	30
5/4 x 10 trim band	1/18'	U26 dipped	12
Misc hardware	$50.00	deck flashing dipped	20 LF
DTT2Z	10	HUC612 dipped	3
1/2 x 7" bolts dipped	10 B + 10 N + 20 W	BC66 dipped	2

Material list sample from
www.houseplans.pro

Bruinier Design	www.houseplans.pro		
Plan sample	Builder ?????		**Page # 9**
Date 1-8-19	Approx 2809 sq ft + decks		
Bedroom 1 deck finish			
2 x 2 cedar pickets	28/3'		
2 x 6 cedar	1/18'		
2 x 4 cedar	2/18'		
4 x 4 cedar	2/8'		
2 x 6 cedar decking ??	9/14'		
5/4 x 10 trim band	1/18'		
Misc hardware	$50.00		
DTT2Z	8		
1/2 x 7" bolts dipped	8 B + 8 N + 16 W		